

Ridge Road Water Main Replacement, Phase 2
 SCHEDULE OF PRICES

| Item | Description | Units | Quantity | Unit Price | Unit Price in Words | Total (Extended) Price |
|------|---|-------|----------|------------|---------------------|------------------------|
| 1 | Mobilization/Demobilization, Site Preparation and Clean-up | LS | 1 | | | |
| 2 | Trench Safety and Shoring Design, Construction, and Maintenance | LS | 1 | | | |
| 3 | Construction Surveying and Asbuilts | LS | 1 | | | |
| 4 | Traffic Control and Pedestrian Safety | LS | 1 | | | |
| 5 | Temporary Erosion and Sedimentation Control (TESC) | LS | 1 | | | |
| 6 | 8-inch AWWA C900 PVC Water Main and Appurtenances | LF | 660 | | | |
| 7 | 8-inch Gate Valve Assembly | EA | 1 | | | |
| 8 | 6-inch Gate Valve Assembly | EA | 0 | N/A | N/A | N/A |
| 9 | 4-inch Gate Valve Assembly | EA | 0 | N/A | N/A | N/A |
| 10 | Fire Hydrant Assembly | EA | 1 | | | |
| 11 | Air and Vacuum Release Valve Assembly | EA | 0 | N/A | N/A | N/A |
| 12 | Permanent Blow-off Assembly | EA | 0 | N/A | N/A | N/A |
| 13 | Connection to Existing Single Water Service | EA | 2 | | | |
| 14 | Connection to Existing Double Water Service | EA | 2 | | | |

Ridge Road Water Main Replacement, Phase 2
 SCHEDULE OF PRICES

| Item | Description | Units | Quantity | Unit Price | Unit Price in Words | Total (Extended) Price |
|---|--|-------|----------|------------|---------------------|------------------------|
| 15 | Connection to Existing Water System | EA | 1 | | | |
| 16 | Abandon Existing Water System | LS | 1 | | | |
| 17 | Crushed Surfacing | TON | 643 | | | |
| 18 | Hot Mix Asphalt (HMA) for Trench Patch | TON | 0 | N/A | N/A | N/A |
| 19 | Hot Mix Asphalt (HMA) for Overlay with Grind | TON | 0 | N/A | N/A | N/A |
| 20 | Final Restoration and Hydroseed | LS | 1 | | | |
| SUBTOTAL (ITEMS 1 TO 20) | | | | | | \$ |
| WASHINGTON STATE SALES TAX (8.60%) | | | | | | \$ |
| TOTAL | | | | | | \$ |